NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
213	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 -b) 6Amps Two way	Each	15.00	100.00	Rupees One Hundred Only
214	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 - c) 6Amps 3way socket	Each	100.00	109.00	Rupees One Hundred Nine Only
215	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 - d) Steeped fan Regulator	Each	80.00	329.00	Rupees Three Hundred Twenty Nine Only
216	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 - e) 16Amps one way switch	Each	75.00	131.00	Rupees One Hundred Thirty One Only
217	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 - f) 6Amps Bell push	Each	10.00	100.00	Rupees One Hundred Only
218	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 - g) 6/16Amps universal socket	Each	33.75	169.00	Rupees One Hundred Sixty Nine Only
	Above 125%	Each	26.25	186.22	Rupees One Hundred Eighty Six and Twenty Two Paise Only
219	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 - h) TV/Telephone socket	Each	15.00	94.00	Rupees Ninety Four Only
220	Supply and fixing metal fan box with round hook	Each	100.00	106.00	Rupees One Hundred Six Only
221	Supply and fixing of 6Amps bell buzzer on existing switch board.	Each	5.00	134.00	Rupees One Hundred Thirty Four Only
222	Supplying following size heavy guage PVC conduit pipe and following thick confirming to IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary - a) 19mm dia 2mm thick	Rmtr	2000.00	49.00	Rupees Forty Nine Only
223	Supplying following size heavy guage PVC conduit pipe and following thick confirming to IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary - b) 25mm dia 2mm thick	Rmtr	1000.00	66.00	Rupees Sixty Six Only
224	Supplying following size heavy guage PVC conduit pipe and following thick confirming to IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary - c) 32mm dia 2.5mm thick	Rmtr	81.25	103.00	Rupees One Hundred Three Only
	Above 125%	Rmtr	18.75	105.75	Rupees One Hundred Five and Seventy Five Paise Only

tractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
225	Supplying heavy gauge pvc conduit pipe ...dia...mm thick with suitable size bends, metal Junction boxes adhesive paste etc..,by groove cutting in the wall and fixing by bracing U & J hooks and Cement plasteriing upto the wall surface and run wirh 18 SWG GI fish wire run throughout the conduit where ever necessary. 19/ 20 mm dia 2mm thick	Rmtr	2000.00	64.00	Rupees Sixty Four Only
226	Supplying heavy gauge pvc conduit pipe ...dia...mm thick with suitable size bends, metal Junction boxes adhesive paste etc..,by groove cutting in the wall and fixing by bracing U & J hooks and Cement plasteriing upto the wall surface and run wirh 18 SWG GI fish wire run throughout the conduit where ever necessary. 25 mm dia 2mm thick	Rmtr	500.00	67.00	Rupees Sixty Seven Only
227	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multisand Copper with low conductor resistance single core wire in open or consealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-A - a) 1.5sqmm	Rmtr	2500.00	21.00	Rupees Twenty One Only
228	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multisand Copper with low conductor resistance single core wire in open or consealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-A b) 2.5sqmm	Rmtr	3000.00	34.00	Rupees Thirty Four Only
229	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multisand Copper with low conductor resistance single core wire in open or consealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-A c) 4sqmm	Rmtr	1862.50	48.00	Rupees Forty Eight Only
	Above 125%	Rmtr	137.50	51.73	Rupees Fifty One and Seventy Three Paise Only
230	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multisand Copper with low conductor resistance single core wire in open or consealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-A f) 6sqmm	Rmtr	20.00	197.00	Rupees One Hundred Ninety Seven Only
231	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.I - Single Door - 8Way SP &N -	Each	5.00	995.00	Rupees Nine Hundred Ninety Five Only
232	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.II - Double Door - 6Way TP & N	Each	10.00	2758.00	Rupees Two Thousand Seven Hundred Fifty Eight Only
233	Supplying, fixing and wiring Earth Leakage Miniature Circuit Breaker (ELMCB) 240/450V uoto 300mA sensitivity on exisiting wood/panel board - 32- 40 Amps 4 pole	Each	1.00	3375.00	Rupees Three Thousand Three Hundred Seventy Five Only
234	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. confirming to IEC 60898 - 5-32A SP MCB	Each	60.00	480.00	Rupees Four Hundred Eighty Only
235	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. confirming to IEC 60898 - 5-32AMPS DB MCB	Each	10.00	976.00	Rupees Nine Hundred Seventy Six Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
236	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. confirming to IEC 60898 - 5-32AMPS TPN MCB	Each	10.00	1778.00	Rupees One Thousand Seven Hundred Seventy Eight Only
237	Supplying Patti type fluorescent tube light fitting of 4' - suitable for 28 W fluorescent tube fitting made out of MS sheet and stove enamelled withHF Electronic Ballast locking type brass contact holder mounted on double fold typebase fully y wired for use on 230V AC supply including T5 fluorescent tube	Each	200.00	769.00	Rupees Seven Hundred Sixty Nine Only
238	Supplying and fixing PBBC bakelite straight or slant batten holder and wiring with 60W/230 VOLTS/18W CFL lamp	Each	70.00	101.00	Rupees One Hundred One Only
239	Supplying and. fixing cast Aluminium round or oblong type bulk head fitting with GI wire guard, glass cover with 15Watts 230V CFL lamp as required	Each	15.00	1094.00	Rupees One Thousand Ninety Four Only
240	Supply of 2'x2' LED recessed luminaire with ...Watts system wattage. Housing shall be with pressure die cast aluminum alloy with corrosion proof resistant polyester power coated. Driver operates with voltage range from 100V to 270V 50/60 Hz with short circuit, overload & mis-wiring protection. Lumen Maintenance of 70% at 50000 Hrs. Injection moulded poly carbonate diffuser for better mechanical stability, light transmission & avoid pot hole effect. Junction temperature shall be < 70 degree Celsius. Driver is on constant current driver @ 0.06A with PF > 0.92 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens with < 80mm depth. 5 years Warranty against any manufacturing defect working under standard electrical condition - LED modular down light 2'x2'-36 watts	Each	10.00	9474.00	Rupees Nine Thousand Four Hundred Seventy Four Only
241	Supplying CFL Mirror light fitting with 1x11W CFL lamp, choke, perspex cover and completely wired for use on 230V 50Hz AC Supply.	Each	18.00	745.00	Rupees Seven Hundred Forty Five Only
242	Supplying of 1440rpm heavy duty eahust fan with bracket blades suitable for operate on 230V 50Hz, AC Supply complete. 12" sweep	Each	10.00	1954.00	Rupees One Thousand Nine Hundred Fifty Four Only
	Above 125%	Each	2.00	2413.95	Rupees Two Thousand Four Hundred Thirteen and Ninety Five Paise Only
243	Supplying capacitor type 48" sweep ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. single phase AC supply confirminf to ISS-374-1979 and with double ball bearing system. Economy Model	Each	80.00	2184.00	Rupees Two Thousand One Hundred Eighty Four Only
244	Supplying wall mounting fan suitable to operate at single phase 230V AC Supply. 400mm sweep	Each	2.00	2913.00	Rupees Two Thousand Nine Hundred Thirteen Only
245	Fixing all types and allcapacities fluorescent / false ceiling/spotlight/ CFLfittings indoor on the wall/ ceiling/rafters / girders using 23/0.0076" twin twisted RVC insulated wires, required nos of round blocks and clamps (if required) a)On wall/ceiling/Rafters/Girders	Each	313.00	113.00	Rupees One Hundred Thirteen Only
246	Fixing a ceiling/Wall mounting fan of all capacities and all types to the existing S hook together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23 / 0.0076 inch PVC insulated twin twisted copper wire and wiring completely.	Each	86.00	160.00	Rupees One Hundred Sixty Only

Contractor

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
247	ing charges of post top/Gate/Garden fitting/ LED on the existing CI/ GI or any other pipe using required size of reducer, wiring using suitable wires etc., complete.	Each	2.00	167.00	Rupees One Hundred Sixty Seven Only
248	Supplying of 1.5TR Spilt air conditioners suitable for operation on AC Supply Single phase 50Hz 230 Volts hermetically sealed compressor with air cooled condensor, moter capcitor & start run capacitors, realy & over load protector internal unit, with one indore & one out door unit. the condencor unit will be place out side the room on the terrace to avoid noise including standerad length of suitable size copper tubing covered with insulation tube (High wall chorded/chordless) suitable capacity 3 core sheathed /PVC Copper cable & battery operated wireless remote Unit. 1.5 Ton Capacity	Each	7.50	53346.00	Rupees Fifty Three Thousand Three Hundred Forty Six Only
	Above 125%	Each	0.50	60923.50	Rupees Sixty Thousand Nine Hundred Twenty Three and Fifty Paise Only
250	Supplying and drawing PVC Flexible one pair telephone unarmoured tinned copper cable - 3 Pair	Rmtr	500.00	18.00	Rupees Eighteen Only
251	Supplying and drawing PVC Insulated Gas injected physical Foam jelly floaded co-Axial TV Cable RG-6	Rmtr	750.00	40.00	Rupees Forty Only
	Above 125%	Rmtr	750.00	40.23	Rupees Forty and Twenty Three Paise Only
252	Supplying & Drawing UTP- CAT 6E-LAN Cable - Group- A	Rmtr	1250.00	26.00	Rupees Twenty Six Only
	Above 125%	Rmtr	250.00	33.34	Rupees Thirty Three and Thirty Four Paise Only
253	Supplying & fixing of network switches - 24 Port Gigabyte (Manageable)	Each	1.00	36382.00	Rupees Thirty Six Thousand Three Hundred Eighty Two Only
254	Design Supplying , erecting testing and commissioning pf 13 passanger / hospital lift with speed of 1.0Mtr per second variable voltage, variable frequency drive, with or without machine room for the available well size, operating at 415V Three phase 50 cycles AC Supply powder coated or stainless steel car enterance door enclosures with flooring car illumination emergencey light intercom and fan as desired by the user, central opening / side opening door with or without attendant operantion, 7 segment display kids buttons call register indicator fireman ddrive, SS Handrails inside car full length infra-red curtain in car door automatic rescue device voice announciation in reginal languages braile buttons with one year warranty and maintenance. the work includes providing shaft scafolding, attending minor builder work such as making nitches of fixing of brackets guide rails, counter weights etc., including obtaining lift running liecence from the compentent authority.	Each	1.00	2532458.00	Rupees Twenty Five Lakh Thirty Two Thousand Four Hundred Fifty Eight Only
255	Supplying erection, testing and commissioning of 3Way 11KV Load Break switch with connected accessories, hardwares etc., suitable for outdoor type complete as per IS standard technical specification. LBS should be approved by BESCOM.	Each	1.00	306693.00	Rupees Three Lakh Six Thousand Six Hundred Ninety Three Only
256	Supplying erection, testing and commissioning of Load Break switch with 4 wire -(with neutral) metering cubicle and connected accessories, hardwares etc., suitable for outdoor type complete as per IS standard technical specification. LBS should be approved by BESCOM.	Each	1.00	367825.00	Rupees Three Lakh Sixty Seven Thousand Eight Hundred Twenty Five Only

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
257	Supplying, erection, testing and commissioning100KVA Capacity Copper wound distribution transformer 11KV/433V with Off Load Tap Switch, Buchholtz relay winding temperature indicator, oil temperature indicator, marshalling box with wiring, magnetic oil level indicator with +5% to -10% steps of 2.5% with HT and LT cable end boxes including all standard accessories as per latest IS standard technical specification.	Each	1.00	377841.00	Rupees Three Lakh Seventy Seven Thousand Eight Hundred Forty One Only
258	Supplying and laying of high tension 11KV cable dry curing & dry cooling with true triple extrusion, simultaniously through a single common head, 3core under ground XLPE cable having stranded compact circular aluminium conductor, screened insulated, insulation screened with extruded semiconducting compound in combination with copper tape, core laid up inner sheathe of PVC tape GI flat strip armoured and overall PVC sheathed with specified IS 7098/11/85 with latest amendments & confirming to the GTP of Group-A 3Cx95Sqmm	Rmtr	62.50	1195.00	Rupees One Thousand One Hundred Ninety Five Only
	Above 125%	Rmtr	37.50	1195.48	Rupees One Thousand One Hundred Ninety Five and Forty Eight Paise Only
259	Supplying and making 11KV(E) Extruded "X" linked for tubing & moulded & cross linked components using heat shrink stress control tube having high permitivity XLPE terminations- INDOOR & OUTDOOR JOINTING KIT & confirming to the GTP. OUT DOOR 3Cx/95/120Sqmm	Kit	2.00	11619.00	Rupees Eleven Thousand Six Hundred Nineteen Only
260	Supplying and making 11KV(E) Extruded "X" linked for tubing & moulded & cross linked components using heat shrink stress control tube having high permitivity XLPE terminations- INDOOR & OUTDOOR JOINTING KIT & confirming to the GTP. IN DOOR 3Cx95/120Sqmm	Kit	6.00	9625.00	Rupees Nine Thousand Six Hundred Twenty Five Only
261	Chemical earthing for grounding, conduits, IC cutouts & other equipments on the meter board by using copper bonded / SS rod with earth enhancing bcakfill compound which is noncorrosive thermally conductive, potential to permissibel limits, superior fault conduction capacity, non toxic, weather resistance & capable of achieving Ohmic value less than one Ohm. Using 10ft copper bonded rod with backfill compound	Each	12.00	8621.00	Rupees Eight Thousand Six Hundred Twenty One Only
262	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required - GI Strip 25x3mm	Rmtr	30.00	89.00	Rupees Eighty Nine Only
263	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required - GI Strip 25x6mm	Rmtr	20.00	136.00	Rupees One Hundred Thirty Six Only
264	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required - Copper Strip 25x3mm	Rmtr	10.00	601.00	Rupees Six Hundred One Only
265	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required - Copper Strip 25x6mm	Rmtr	10.00	1170.00	Rupees One Thousand One Hundred Seventy Only
266	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tap armoured cable with PVC outer sheathing 1.1 KV class - Class 'A' PVC cable - 4Core 10Sqmm	Rmtr	62.50	137.00	Rupees One Hundred Thirty Seven Only
	Above 125%	Rmtr	17.50	149.44	Rupees One Hundred Forty Nine and Forty Four Paise Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
267	Applying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tap armoured cable with PVC outer sheathing 1.1 KV class - Class 'A' PVC cable - 3.5Core 150Sqmm	Rmtr	50.00	756.00	Rupees Seven Hundred Fifty Six Only
268	Labour charges for layingof 1.1 KVclass UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall/ on pole as required. In existing trench/duct - 6sqmm to 16sqmm	Rmtr	80.00	12.00	Rupees Twelve Only
269	Labour charges for layingof 1.1 KVclass UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall/ on pole as required. On wall/structure - 6sqmm to 16sqmm	Rmtr	15.00	36.00	Rupees Thirty Six Only
270	Labour charges for layingof 1.1 KVclass UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall/ on pole as required. On wall/structure - 185sqmm to 240sqmm	Rmtr	10.00	51.00	Rupees Fifty One Only
271	Digging of trench of 0.6m deep x 0.50 mtr wide refiling the trench to the required ground level and consolidating etc., complete. in soil (ordinary)	Rmtr	20.00	90.00	Rupees Ninety Only
272	Providing and filling sand in excavated trench to cover already laid UGcable to a depth of 150mm alround the cable.	Rmtr	20.00	118.00	Rupees One Hundred Eighteen Only
273	Providing and laying in position 100mm dia stone ware pipe in exisitng trench.	Rmtr	20.00	256.00	Rupees Two Hundred Fifty Six Only
274	Supplying and fixing of class A (mediumduty) GI pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UGcable of 1.1 KVclass.80mm	Rmtr	12.00	816.00	Rupees Eight Hundred Sixteen Only
275	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KVclass (metal only) - 75mm dia	Each	2.00	590.00	Rupees Five Hundred Ninety Only
276	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KVclass (metal only) - 100mm dia	Each	5.00	1147.00	Rupees One Thousand One Hundred Forty Seven Only
278	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes - 16Sqmm Long Barrel	Each	20.00	13.00	Rupees Thirteen Only
279	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes - 25Sqmm Long Barrel	Each	5.00	24.00	Rupees Twenty Four Only
280	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes - 150Sqmm Long Barrel	Each	10.00	278.00	Rupees Two Hundred Seventy Eight Only
281	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes - 185Sqmm Long Barrel	Each	10.00	389.00	Rupees Three Hundred Eighty Nine Only
282	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	Rmtr	36.00	1066.00	Rupees One Thousand Sixty Six Only
283	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint	Sqmt	42.00	888.00	Rupees Eight Hundred Eighty Eight Only

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
284	LT Kiosk Panel Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of overload and short circuit with the thermal magnetic/micro processor release and earth fault as per IS -13947 (Icu=Ics) 320 -400Amps 4Pole 50kA	Each	1.00	28175.00	Rupees Twenty Eight Thousand One Hundred Seventy Five Only
285	Supplying, fixing of LED type panel board indicating lamp with required colour suitable for 220VA.C 50HZ 12/24V DC.	Each	3.00	508.00	Rupees Five Hundred Eight Only
286	Supplying 100 amps rated 3phase with neutral bus bar using requiemedcapacity electrolyticaluminium strips covered with heat shrinkable couloured PVC sleeve, mounted on phenolic/FRP/DMC insulator whcih are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete 100Amps 4x50x10mm Alluminium Strips	Rmtr	3.00	2454.00	Rupees Two Thousand Four Hundred Fifty Four Only
287	Supplying and fixing angle iron frame work fabricated out of M.S.angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint	Rmtr	26.00	546.00	Rupees Five Hundred Forty Six Only
288	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover,equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete 14SWG	Sq Cm	56000.00	0.54	Fifty Four Paise Only
289	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc.and fixing on existing wood or metal box using N.F. screws.	Sq Cm	6000.00	0.36	Thirty Six Paise Only
290	Main Panel -Annexure-B ,Incoming Supplying of On load change over switches 4poles, AC- 23A duty, 415V, 50Hz, AC supply. 400Amps	Each	1.00	33500.00	Rupees Thirty Three Thousand Five Hundred Only
291	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. 320 -400Amps 4Pole 50kA	Each	1.00	28175.00	Rupees Twenty Eight Thousand One Hundred Seventy Five Only
292	Supplying, fixing and wiring earth leakage relay with core balanced current transformer suitable for single phase 50 Hz AC with latest microcontroller based, digital readout of pecentage leakage current, programable delay/auto/manual reset facility suitable to mount on DIN rail/ flush mounting on panel board.	Each	1.00	9194.00	Rupees Nine Thousand One Hundred Ninety Four Only
293	Supplying of multi function digital Meter with three line back light LCD type display of voltage, Current, frequency,Power, power factor,KVA, KWH,KVAR suitable for 3 phase, 4 wire LT network with IP 54 degree of protection and completely wired as required with communication port and class 0.5s accuracy.	Each	1.00	9199.00	Rupees Nine Thousand One Hundred Ninety Nine Only
294	Supplying, fixing and wiring 50/5 to 400/5 Amps 5VA burden Current Transformer. Class 0.5 accurecy with tape wound	Each	3.00	555.00	Rupees Five Hundred Fifty Five Only
295	Supplying, fixing of LED type panel board indicating lamp with required colour suitable for 220VA.C 50HZ 12/24V DC.	Each	3.00	508.00	Rupees Five Hundred Eight Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
296	Supplying 400 amps rated 3phase with neutral bus bar using requiemedcapacity electrolyticaluminium strips covered with heat shrinkable couloured PVC sleeve, mounted on phenolic/FRP/DMC insulator whcih are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete. 400Amps 4x50x10mm Alluminium Strips	Rmt	6.00	4395.00	Rupees Four Thousand Three Hundred Ninety Five Only
297	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete.125Amps 4Pole 25kA	Each	1.00	8474.00	Rupees Eight Thousand Four Hundred Seventy Four Only
298	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, e nergy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 63A TPN MCB	Each	12.00	2225.00	Rupees Two Thousand Two Hundred Twenty Five Only
299	Supplying ,fixing and wiring heavy duty low voltage capacitors conforming to IS 2834. 3 phase, 400/440 volts grade, for power factor improvement of rotating machinery. Cost per KVAR.	KVAR	1.00	476.00	Rupees Four Hundred Seventy Six Only
300	Supplying and fixing angle iron frame work fabricated out of M.S.angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.	Rmtr	30.00	546.00	Rupees Five Hundred Forty Six Only
301	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover,equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete 14SWG	Sq Cm	148000.00	0.54	Fifty Four Paise Only
302	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc.and fixing on existing wood or metal box using N.F. screws.	Sq Cm	40000.00	0.36	Thirty Six Paise Only
303	Lift Panel, Annexure-E, Incoming,Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. 63Amps 4Pole 25kA	Each	1.00	6677.00	Rupees Six Thousand Six Hundred Seventy Seven Only
304	Supplying, fixing and wiring 3 Phase Digital Ammeter/Voltmeter	Each	2.00	1407.00	Rupees One Thousand Four Hundred Seven Only
305	Supplying, fixing and wiring rotary selector switch suitable for ammeter	Each	1.00	198.00	Rupees One Hundred Ninety Eight Only
306	Supplying, fixing and wiring rotary selector switch suitable for voltmeter	Each	1.00	161.00	Rupees One Hundred Sixty One Only
307	Supplying, fixing and wiring 50/5 to 400/5 Amps 5VA burden Current Transformer. Class 0.5 accurecy with tape wound	Each	3.00	555.00	Rupees Five Hundred Fifty Five Only
308	Supplying, fixing of LED type panel board indicating lamp with required colour suitable for 220VA.C 50HZ 12/24V DC.	Each	3.00	508.00	Rupees Five Hundred Eight Only
309	Supplying 100 amps rated 3phase with neutral bus bar using requiemedcapacity electrolyticaluminium strips covered with heat shrinkable couloured PVC sleeve, mounted on phenolic/FRP/DMC insulator whcih are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete.100Amps 4x30x6mm Alluminium Strips	Rmtr	1.00	2454.00	Rupees Two Thousand Four Hundred Fifty Four Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
310	OutGoings:-Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 5-32A SP MCB	Each	3.00	480.00	Rupees Four Hundred Eighty Only
311	OutGoings:-Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 5-32A DP MCB	Each	3.00	976.00	Rupees Nine Hundred Seventy Six Only
312	OutGoings:-Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 40-63A TPN MCB	Each	1.00	2225.00	Rupees Two Thousand Two Hundred Twenty Five Only
313	Supplying and fixing angle iron frame work fabricated out of M.S.angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.40x40x6mm	Rmtr	14.00	546.00	Rupees Five Hundred Forty Six Only
314	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover,equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete 14SWG	Sq Cm	32000.00	0.54	Fifty Four Paise Only
315	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc.and fixing on existing wood or metal box using N.F. screws.	Sq Cm	6000.00	0.36	Thirty Six Paise Only
316	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Nos	16.00	6300.00	Rupees Six Thousand Three Hundred Only
317	Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests, 100mm S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Nos	8.00	5383.00	Rupees Five Thousand Three Hundred Eighty Three Only
318	Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Nos	16.00	4824.00	Rupees Four Thousand Eight Hundred Twenty Four Only
319	Providing and fixing white vitreous china clay, flat back or half stall urinal basin of size 580x380x350mm in the range of two with 7.5 litres P.V.C automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps, C.I. trap with outlet grating and other couplings in C.P brass painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Nos	12.00	10323.00	Rupees Ten Thousand Three Hundred Twenty Three Only

Contractor

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
320	Providing fixing C.P brass towel rail 600mm length, 20mm dia with C.P brackets,fixed to wooden cleats with C.P brass screws including cost of materials,labour complete as per specifications.Make: Jaquar, Range-continental ,	Unit	12.00	881.00	Rupees Eight Hundred Eighty One Only
321	Providing and fixing 600x450mm bevellead edge mirror of superior glass with 6mm hard board backing and fixed to wooden cleats with C.P screws, washers, including cost of materials, labour complete as per specifications.	Unit	13.75	1553.00	Rupees One Thousand Five Hundred Fifty Three Only
	Above 125%	Unit	2.25	1329.97	Rupees One Thousand Three Hundred Twenty Nine and Ninety Seven Paise Only
322	Supply, fixing, testing and commissioning of 20 mm CP brass bib cock with wall flange and suitable length extension pipe etc,. complete as per specification.	Nos	20.00	302.00	Rupees Three Hundred Two Only
323	Providing and fixing in position brass stop cock of approved quality 20 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. etc,. ,. complete as per specification.	Nos	20.00	199.00	Rupees One Hundred Ninety Nine Only
324	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms	Nos	32.00	310.00	Rupees Three Hundred Ten Only
325	KSRB 2-2.1: Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m.after breaking of clods complete as per specification. Specification.	Cum	36.00	235.00	Rupees Two Hundred Thirty Five Only
326	Providing & fixing Chorinated Poly Venyl Chloride (CPVC) 20 mm dia pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00m spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and cost of cutting chases and making good the same including testing of joints complete. (concealed work including cutting chases and good the walls etc.) - 20mm Dia	Rmt	80.00	261.00	Rupees Two Hundred Sixty One Only
327	Providing and fixing chorinated poly venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (External work) - 20mm Dia	Rmtr	50.00	155.00	Rupees One Hundred Fifty Five Only
328	Providing and fixing chorinated poly venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (External work) - 25mm Dia	Rmtr	150.00	205.00	Rupees Two Hundred Five Only

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
329	Providing and fixing chorinated poly venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (External work) - 32mm Dia	Rmtr	62.50	267.00	Rupees Two Hundred Sixty Seven Only
	Above 125%	Rmtr	137.50	259.79	Rupees Two Hundred Fifty Nine and Seventy Nine Paise Only
330	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 32mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. do'- with 32 mm dia (Screwed ends)	Nos	4.00	1208.00	Rupees One Thousand Two Hundred Eight Only
331	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Nos	1.00	745.00	Rupees Seven Hundred Forty Five Only
332	Supply, installation, testing and commissioning electrically driven SUBMERSIIBLE pump of capacity 2HP / 1.5 KW with 12 stages Single phase, 50Hz, 400/440V AC supply with necessary non-return valves, butterfly valves,Pressure gauge & Pressure switch with inter-connecting wiring etc., complete as per standard design. (For pumping the domestic water from the underground sump to the overhead water tank). Make/Brand :ATALANTA,SUGUNA, C.R.I.,KIRLOSKAR AND OTHER EQUIVALENT PUMPS...	Nos	1.00	19243.00	Rupees Nineteen Thousand Two Hundred Forty Three Only
333	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer Black or Blue and inner White layer of approved quality and make, conforming to I.S.I./ISO/SSI specifications.	Each	2000.00	7.00	Rupees Seven Only
334	Providing and fixing to wall, ceiling and floor unplasticised 110 mm dia PVC Pipes of 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications - 110 mm Dia	Rmtr	225.00	511.00	Rupees Five Hundred Eleven Only
335	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,with 110mm outer dia	Rmtr	87.50	854.00	Rupees Eight Hundred Fifty Four Only
	Above 125%	Rmtr	2.50	683.95	Rupees Six Hundred Eighty Three and Ninety Five Paise Only
336	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,with 160mm outer dia	Rmtr	50.00	1800.00	Rupees One Thousand Eight Hundred Only
337	Constructing brick masonry inspection chamber 600 x 600mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 600 x 600mm	Each	8.00	11116.00	Rupees Eleven Thousand One Hundred Sixteen Only
	EIRL Items				

Executive Engineer/P

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
338	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications	Sqm	888.00	444.44	Rupees Four Hundred Forty Four and Forty Four Paise Only
339	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over 20mm thk 1:4CM, & Jointed with neat cement slurry mixed with pigment to much shade of granite slabs including laying POP on finished surface and cleaning the surface including the cost of all materials and labour etc, complete as per specification.	Sqm	1526.50	3399.12	Rupees Three Thousand Three Hundred Ninety Nine and Twelve Paise Only
340	Constructing brick masonry inspection chamber 450x450mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 450x450 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M15 with 20mm and downsize granite metal, foundation concrete M5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications	Nos	4.00	8769.67	Rupees Eight Thousand Seven Hundred Sixty Nine and Sixty Seven Paise Only
341	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand Pump, MWS or PWSS by vertical electrical sounding by adopting Venner on Schlumberger's method, including reconnaissance survey of geological formation, geophysical investigation of existing ground water in the vicinity, its quality quantity & acceptability of the users indicating the location site, recommended depth of casing pipe required to seal the top unconsolidated formation, including an extra depth of 1.0 mtrs in consolidated formation for proper seating of casting depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc.	Nos	1.00	4331.32	Rupees Four Thousand Three Hundred Thirty One and Thirty One Paise Only
342	Sinking of Borewell of 165mm dia clear, using superfast Hydraulic rig of capacity 250 PSIG and above 900 CFM and above in all strata including over burden upto 20m fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of Rig & supporting vehicle, crew charges & cost of consumables etc., complete including yield testing and the final depth with a minimum working compressor for one hour (excluding cost of casting pipes, collars and cap etc.)0.00 to 50.00mtr	Rmtr	50.00	398.88	Rupees Three Hundred Ninety Eight and Eighty Seven Paise Only
343	50.00 to 100.00mtrs	Rmtr	50.00	508.08	Rupees Five Hundred Eight and Seven Paise Only
344	100.00 to 150.00mtrs	Rmtr	50.00	524.17	Rupees Five Hundred Twenty Four and Seventeen Paise Only
345	150.00 to 200.00mtrs	Rmtr	50.00	618.43	Rupees Six Hundred Eighteen and Forty Three Paise Only

ntractor

Executive Engineer(P)

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
346	200 to 250.00mtrs	Rmtr	50.00	728.78	Rupees Seven Hundred Twenty Eight and Seventy Eight Paise Only
347	250 to 300.00mtrs	Rmtr	50.00	804.65	Rupees Eight Hundred Four and Sixty Five Paise Only
348	Supply of ISI mark 175 mm nominal bore, plain end steel casing pipe grade of steel Fe 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, eletric resistence welded steel tube material and confirming to IS 1387/1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5 to 7 mts. Both ends threaded confirming to IS 554/1985, one end fixed with socket conforming to IS 4270:2001 and the other end with screwed pipes. All pipes shall be reasonably free from defects. The tubes shall be reasonably straight should be with ISI marking, weighing 25.10Kg/mtr (inclusive of all taxes and duties). Prices including collar medium duty	Rmtr	30.00	1523.09	Rupees One Thousand Five Hundred Twenty Three and Eight Paise Only
349	Providing and fixing 175mm dia borewell cap medium class(MR)	Nos	1.00	114.95	Rupees One Hundred Fourteen and Ninety Five Paise Only
350	M.S. Casing pipe collars "B" class (MR)	Nos	5.00	172.43	Rupees One Hundred Seventy Two and Forty Two Paise Only
351	Supply and delivery at site brand new submersible PUMPSET suitable for borewell of 150mm dia and haing declared duty conditions as detailed below nd satisfying performance characteristic for pump and motar as declared by Bureau of Indian Standards. The pump should confirm to IS 928 / 55 (with all its latest amendments) and should bear the ISI certification mark is 928/55. The pumpset should consist of bronze impellers, Discharge : 750 lph, Head L102.88 mts 10HP /7.5KW 20 Stage. ATLANTA,Suguna, CRI, Kirloskar or other equivalent pumps	Rmtr	1.00	57423.27	Rupees Fifty Seven Thousand Four Hundred Twenty Three and Twenty Seven Paise Only
352	Supplying and drawing 3 core flat PVC sheathed Submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor conforming to table 3clause 5 of IS :8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts.(Group B) -3C X 6.0Sq.mm	Rmtr	300.00	187.94	Rupees One Hundred Eighty Seven and Ninety Four Paise Only
353	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair of supporting clams, borewell cap, cable clips with bolts, nuts, valve gauges etc., involved in the job. (Necessary G.I.Pipe and specials will be supplied by the board at the site free of cost)(CE (M) BWSSB, Letter No.BWSSB/CE(M)ACE(M)-II/TA-8/9194/2008-09 dated 21/1/09)	Nos	2.00	3000.00	Rupees Three Thousand Only
354	Supplying and fixing 50mm GI Union.	Nos	2.00	257.14	Rupees Two Hundred Fifty Seven and Fourteen Paise Only
355	Supplying and fully automatic star-delta unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base late held in steel enclosure for use on 440/440 volts 3 phase and wired after to the existing wooden board for motor 15.0 HP	Nos	1.00	9509.81	Rupees Nine Thousand Five Hundred Nine and Eighty One Paise Only

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
356	ction of single phase preventor ammeters/ including fixing selector switch/ current operated earth leakage circuit breakers voltage operated earth leakage circuit breakers voltage operated circuit breaker/ above 100A fuse channel set (3 Nos) HRC fuses above 100A (3 Nos) including wiring using suitable capacity wires, bolts, nuts, screws etc, including transportation charges from stores to spot	Nos	1.00	180.47	Rupees One Hundred Eighty and Forty Seven Paise Only
357	Fabricating, supplying and mounting 1200x900x350 mm MS box made out of 18 SWG suitable for floor/ wall mounting, fully weather proof with double stanted top as per drawing with provision for better heat dissipation provided with hinged front cover with clear clamped to the door on EB meter side to facilitate meter reading, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with approved colour enameled metal plant etc, complete box of 36200 Sqcm, @ Rs.0.20 18 SWG	Nos	1.00	9041.97	Rupees Nine Thousand Forty One and Ninety Six Paise Only
358	Supplying and fixing miniature circuit breakers/isolators on existing MCB distribution boards using necessary fixing materials and wiring complete as required - 40 to 63 amps triple pole	Nos	1.00	778.21	Rupees Seven Hundred Seventy Eight and Twenty One Paise Only
359	Supplying andrunning of GI copper strip or grounding connection using necessary fixing material required 600x600c3mm GI plate	Nos	1.00	901.21	Rupees Nine Hundred One and Twenty Paise Only
360	Supplying and fixing Porcelain fuse channel with cut out on the existing wooden /panel using necessary nuts bolts and washer etc., complete....	Nos	3.00	137.94	Rupees One Hundred Thirty Seven and Ninety Four Paise Only
361	Providing and fixing in position brass gate valve with C.I. Wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete s per specifications. Specification No.KBS 13.2.6/ 13.3	Nos	1.00	2158.90	Rupees Two Thousand One Hundred Fifty Eight and Eighty Nine Paise Only
362	Supplying and laying of L.T.U.G cable having aluminium conductor PVC insulated sheathed galvanised steel wire/steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 Sqmm PVC cable	Mtr	25.00	149.44	Rupees One Hundred Forty Nine and Forty Three Paise Only
363	Labour charges for Laying of 1.1 KV Class UG cable 6 Sqmm to 16 sqmm	Mtr	25.00	13.66	Rupees Thirteen and Sixty Five Paise Only
364	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating in Hard soil etc., complete. complete as per specifications and direction of the Engineer-in-Charge	Cum	20.00	87.36	Rupees Eighty Seven and Thirty Six Paise Only
365	Supplying and fixing Class-A (Medium duty) -GI pipe wall thickness not less than 3.25mm on pole/wall/Drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 65mm	Mtr	10.00	649.47	Rupees Six Hundred Forty Nine and Forty Six Paise Only
366	Supplying and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled wiith necessary bitumen / insulating compound complete. With terminals, clamps, bolts nuts and washers etc.complete for 16 Sqmm as per specification	Nos	1.00	310.37	Rupees Three Hundred Ten and Thirty Six Paise Only
367	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m after breaking of clods complete as per specification.spacification. No.KBS 2.1(b) / 2.3.5	Cum	22.50	371.20	Rupees Three Hundred Seventy One and Nineteen Paise Only

ntractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
368	Providing and Installing at site work P.V.C Including cost of pipe and specials and Labour, including lowering into trenches, laying true to line level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe allround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., Complete, PVC pipes 63mmdia of 6kg/cm2	Rmtr	50.00	128.74	Rupees One Hundred Twenty Eight and Seventy Four Paise Only
369	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specificifictions.	Cum	16.87	150.22	Rupees One Hundred Fifty and Twenty Two Paise Only
370	Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1	Cum	1708.00	109.66	Rupees One Hundred Nine and Sixty Six Paise Only
371	Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 50mm ia nominal bore with fittings (medium grade weight 1.27 Kg/mtr) B class including cost of all materials, labour charges, HOM of equipment and testing complete as per specifications.	Rmtr	260.00	481.69	Rupees Four Hundred Eighty One and Sixty Nine Paise Only

Executive Engineer (Project)
'Rajarajeshwarinagara zone
BBMP

Contractor

Executive Enginee

Scanned with CamScanner